

BILLS OF QUANTITY

NAME OF THE WORK:-

Construction of Sub center at Bhandarpuri of Jharbandh
block in the district of Bargarh for the year 2021-22.

AMOUNT PUT TO TENDER :-

Rs 1957106.00

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	RATE IN FIGURE	AMOUNT (In Rs)
1	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	100.01	Cum	186.40	(Rupees One Hundred Eighty Six and Forty Paise Only)	18641.86
2	Filling foundation and plinth with good coarse sand including watering & ramming as directed by the Engineer in charge	58.52	Cum	328.69	(Rupees Three Hundred Twenty Eight and Sixty Nine Paise Only)	19234.94
3	Cement Concrete M10(1:3:6) with 4cm size hard granite metal including cost, conveyance, royalty, taxes, watering and curing etc. complete.	27.88	Cum	4178.42	(Rupees Four Thousand One Hundred Seventy Eight and Forty Two Paise Only)	116494.35
4	Cement concrete (1 : 2 : 4) using 12 mm size HG CB chips including laying lowering concrete, watering and curing & cost carriage royalty and taxes of all materials etc.	6.93	Cum	5526.27	(Rupees Five Thousand Five Hundred Twenty Six and Twenty Seven Paise Only)	38297.05
5	RCC wok of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying					
5.1	Column Base	13.04	Cum	4646.40	(Rupees Four Thousand Six Hundred Forty Six and Forty Paise Only)	60589.06
5.2	Column(Ground Floor)	4.97	Cum	11850.89	(Rupees Eleven Thousand Eight Hundred Fifty and Eighty Nine Paise Only)	58898.92
5.3	Column(First Floor)	1.54	Cum	13406.11	(Rupees Thirteen Thousand Four Hundred Six and Eleven Paise Only)	20645.41
5.4	Plinth Beam	4.99	Cum	5014.85	(Rupees Five Thousand Forteen and Eighty Five Paise Only)	25024.10
5.5	Lintel(Ground Floor)	2.64	Cum	8280.55	(Rupees Eight Thousand Two Hundred Eighty and Fifty Five Paise Only)	21860.65
5.6	Lintel(First Floor)	0.08	Cum	9121.71	(Rupees Nine Thousand One Hundred Twenty One and Seventy One Paise Only)	729.74
5.7	Chhaja	9.66	Sqm	759.24	(Rupees Seven Hundred Fifty Nine and Twenty Four Paise Only)	7334.26
5.8	Shelve	8.29	Sqm	724.21	(Rupees Seven Hundred Twenty Four and Twenty One Paise Only)	6003.70
5.9	Roof Beam	3.62	Cum	11850.89	(Rupees Eleven Thousand Eight Hundred Fifty and Eighty Nine Paise Only)	42900.22

5.10	Roof Slab	13.37	Cum	8840.40	(Rupees Eight Thousand Eight Hundred Forty and Forty Paise Only)	118196.15
5.11	Stair Case	1.24	Cum	8405.21	(Rupees Eight Thousand Four Hundred Five and Twenty One Paise Only)	10422.46
6	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.(Ground Floor)	46.10	Qtl	7530.63	(Rupees Seven Thousand Five Hundred Thirty and Sixty Three Paise Only)	347162.04
7	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.(First Floor)	2.52	Qtl	7621.27	(Rupees Seven Thousand Six Hundred Twenty One and Twenty Seven Paise Only)	19205.60
8	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum.(In foundation)	24.98	Cum	4109.99	(Rupees Four Thousand One Hundred Nine and Ninety Nine Paise Only)	102667.55
9	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum.(In Superstructure-Ground Floor)	39.58	Cum	4143.32	(Rupees Four Thousand One Hundred Forty Three and Thirty Two Paise Only)	163992.61
10	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum.(In Superstructure-First Floor)	14.64	Cum	4405.17	(Rupees Four Thousand Four Hundred Five and Seventeen Paise Only)	64491.69
11	12 mm thick cement plaster in cement mortar (1:6) out side/face brick walls etc complete.(Ground Floor)	300.74	Sqm	134.22	(Rupees One Hundred Thirty Four and Twenty Two Paise Only)	40365.32
12	12 mm thick cement plaster in cement mortar (1:6) out side/face brick walls etc complete.(First Floor)	118.74	Sqm	137.47	(Rupees One Hundred Thirty Seven and Forty Seven Paise Only)	16323.19
13	16 mm thick cement plaster in CM (1: 6) over brick work inside surface of the wall including cost carriage royalty taxes and watering & curing etc. complete(Ground Floor)	208.84	Sqm	192.02	(Rupees One Hundred Ninety Two and Two Paise Only)	40101.46
14	16 mm thick cement plaster in CM (1: 6) over brick work inside surface of the wall including cost carriage royalty taxes and watering & curing etc. complete(First Floor)	26.34	Sqm	196.86	(Rupees One Hundred Ninety Six and Eighty Six Paise Only)	5185.29
15	Supplying, fitting and fixing of M.S. door, window and grill gate ... etc. complete as per direction of Engineer in charge..	1353.63	Kg	82.18	(Rupees Eighty Two and Eighteen Paise Only)	111241.31
16	Supplying, fitting and fixing of M.S.grill for window,ventilator ... etc. complete as per direction of Engineer in charge..	390.00	Kg	70.59	(Rupees Seventy and Fifty Nine Paise Only)	27530.10
17	Labour charges for fitting and fixing in position of M.S. Grill Door, Window grills & collapsible Gate	50.42	Sqm	70.80	(Rupees Seventy and Eighty Paise Only)	3569.74
18	Supplying, fitting and fixing of M.S square pipe of size 2"X2" for Purlin section of approved quality with cost of all charges etc all complete.	0.41	Qtl	8000.00	(Rupees Eight Thousand Only)	3300.68

19	Supplying, fitting and fixing of colour coated durashine roofing sheet of 0.45 mm thick of approved quality and size with cost of all charges etc. all complete.	11.18	Sqm	850.00	(Rupees Six Hundred Fifty Only)	7267.94
20	Supplying, fitting & fixing of window (siding type made up alminum section 151-154,151-155, as windows frame section No.151-155, 151-153 nad 151-167 as shutter framw with 5mm thik black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes labour T & P etc complete as per direction of Enginner in charge.	1.49	Sqm	3779.90	(Rupees Three Thousand Seven Hundred Seventy Nine and Ninety Nine Paise Only)	5632.19
21	Supplying, fitting, fixing of stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32x32x2mm @0.90 mtr. C/C and stainless square pipe bracing of size 32x32x2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc required for the coplete in all respect.	5.79	Rmt	3805.37	(Rupees Three Thousand Eight Hundred Five and Thirty Seven Paise Only)	22033.07
22	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete excluding cost of precast tiles.(Ceramic Tiles)	105.22	Sqm	1049.79	(Rupees One Thousand Forty Nine and Seventy Nine Paise Only)	110458.90
23	Providing and fixing vitrified tiles in floors, treads of steps and landing on 20mm th bed of cement mortar (1:4) (1 cement:4 sand) jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing, polishing including cost of tiles, conveyance, taxes & labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge	96.13	Sqm	941.18	(Rupees Nine Hundred Forty One and Eighteen Paise Only)	90475.63
24	20mm thick Cement plaster in C.M. (1:4) in grading plaster over roof slab including cost of all labour, materials etc. complete in all respect including 1% cess as per direction of Engineer-in-charge.	104.53	Sqm	242.56	(Rupees Two Hundred Forty Two and Fifty Six Paise Only)	25354.80
25	Priming one coat two wall surafce using water bound cement primer including cost, conveyance all materilas, labour and T & P etc complete.	812.32	Sqm	60.02	(Rupees Sixty and Two Paise Only)	48755.45
26	Finishing surface of walls with Acrylic putty (water based) of approved make & finished smooth & even surface to receive painting including cost of materials taxes labour etc.	812.32	Sqm	71.75	(Rupees Seventy One and Seventy Five Paise Only)	58283.96
27	Distempering two coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper.	737.44	Sqm	65.33	(Rupees Sixty Five and Thirty Three Paise Only)	48176.96

28	Finishing walls with water proofing Weather coat of approved shade on new work two coat over a coat of primer to give an even shade including cost of paint	208.75	Sqm	67.24	(Rupees Sixty Seven and Twenty Four Paise Only)	14036.35
29	Painting two coats with good enamel paint over a coat of primer / red oxide on iron works including cost, conveyance & taxes of all materials, T&P, labour charges etc complete	83.70	Sqm	193.80	(Rupees One Hundred Ninety Three and Eighty Paise Only)	16221.06
Total: 29 (Twenty Nine Items) Only						Rs.1967106.75

Or Say **Rs.1967106.00**

(Rupees Nineteen Lakh Fifty Seven Thousand One Hundred Six) Only


Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:-Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost upto two decimal points only.

CONDITIONS:-All Materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B:-GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minium grade of cement OPC, TMT High strength steel Fe-500.


A.E(NHM)
BARGARH


PROJECT DIRECTOR
DRDA BARGARH

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of

Rs. _____

_____ only(both in figures and words).

CONTRACTOR

BILLS OF QUANTITY

NAME OF THE WORK:-

Establishment of HWC at SC Jhar in Sohela block of Bargarh district for 2021-22.

AMOUNT PUT TO TENDER :-

Rs 354195.00

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	RATE IN FIGURE	AMOUNT (In Rs)
1	Removing old grading plaster from roof slab, cleaning the surface, lowering and removing the debris within 50M lead.	61.56	Sqm	60.20	(Rupees sixty and twenty paise only)	3705.91
2	Dismantling and removing 2.5cm th A.S.flooring including stacking the useful materials for reuse and ramming the debris with in 50m lead etc with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	21.83	Sqm	77.68	(Rupees seventy seven and sixty eight paise only)	1695.75
3	Removing old lime or cement plaster from walls including racking out joints 12mm deep and removing debris etc. with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	20.63	Sqm	38.84	(Rupees thirty eight and eighty four paise only)	801.27
4	6mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment per 1 sqm	7.80	Sqm	130.75	(Rupees one hundred thirty and seventy five paise only)	1019.85
5	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	15.26	Cum	186.40	(Rupees one hundred eighty six and forty paise only)	2844.46
6	Supplying and filling in foundation and plinth with sand well watered & rammed with cost ,conveyance, royalty & taxes of all materials and labour required for the work as per specification and including 1% cess as per direction of the Engineer-in-Charge.	4.81	Cum	328.69	(Rupees three hundred twenty eight and sixty nine paise only)	1581.00
7	Cement Concrete of proportion(1:3:6) in foundation and plinth using 4cm size clean hard black granite metal of approved quality from approved quarry including hoisting, lowering and laying in layers not exceeding 15cm thick to the required level, ramming watering and curing etc.complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	5.81	Cum	4095.79	(Rupees four thousand ninety five and seventy nine paise only)	23796.54
8	Cement concrete (1 : 2 : 4) using 12 mm size HG CB chips including laying lowering concrete, watering and curing & cost carriage royalty and taxes of all materials etc.	3.11	Cum	5429.89	(Rupees five thousand four hundred twenty nine and eighty nine paise only)	16886.96
9	2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size h.b.g. Chips per1 Sqm.	5.57	Sqm	269.42	(Rupees two hundred sixty nine and forty two paise only)	1500.67

10	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum. (In foundation)	5.54	Cum	4063.23	(Rupees four thousand sixty three and twenty three paise only)	22510.29
11	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum. (In Superstructure)	6.21	Cum	4096.56	(Rupees four thousand ninety six and fifty six paise only)	25439.64
12	12 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including waterreing and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	27.48	Sqm	133.59	(Rupees one hundred thirty three and fifty nine paise only)	3671.05
13	16 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including waterreing and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	34.17	Sqm	191.27	(Rupees one hundred ninety one and twenty seven paise only)	6535.70
14	Supplying, fitting and fixing of M.S. door, window and grill gate ... etc. complete as per direction of Engineer in charge..	314.48	Kg	82.18	(Rupees eighty two and eighteen paise only)	25843.97
15	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete excluding cost of precast ties. (Ceramic Tiles)	20.63	Sqm	1047.39	(Rupees one thousand forty seven and thirty nine paise only)	21607.66
16	Providing and fixing vitrified tiles in floors, treads of steps and landing on 20mm th bed of cement mortar (1:4) (1 cement:4 sand) jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing, polishing including cost of tiles, conveyance, taxes & labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge	21.83	Sqm	939.27	(Rupees nine hundred thirty nine and twenty seven paise only)	20504.26
17	Providing & laying water proofs with polymeric bituminous membrance (Plastic felt) including priming the surface with bituminous primer including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	61.56	Sqm	315.38	(Rupees three hundred fifteen and thirty eight paise only)	19414.79
18	Priming one coat two wall surafce using water bound cement primer including cost, conveyance all materilas, labour and T & P etc complete.	61.64	Sqm	60.02	(Rupees sixty and two paise only)	3699.63
19	Finishing surface of walls with Acrylic putty (water based) of approved make & finished smooth & even surface to receive painting including cost of materials taxes labour etc.	644.30	Sqm	71.75	(Rupees seventy one and seventy five paise only)	46228.53

20	Distemping two coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper.	346.49	Sqm	125.35	(Rupees one hundred twenty five and thirty five paise only)	43432.52
21	Finishing walls with water proofing Weather coat (I.S.I.) of approved shade on old/new work two coat over a coat of primer to give an even shade including cost of Weather coat.	359.45	Sqm	127.26	(Rupees one hundred twenty seven and twenty six paise only)	45743.61
22	Painting two coats over a coat of primer with approved paint on wood work & Iron work. (Old & New)	81.17	Sqm	193.80	(Rupees one hundred ninety three and eighty paise only)	15730.75
					Total	Rs.354194.81
					Or Say	Rs.354195.00

(Rupees three lakh fifty four thousand one hundred ninety five) Only

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:-Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost upto two decimal points only.

CONDITIONS:-All Materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B:-GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minium grade of cement OPC, TMT High strength steel Fe-500.


A.E. (NHM)
BARGARH


PROJECT DIRECTOR
DRDA BARGARH

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of

Rs. _____

_____ only (both in figures and words).

CONTRACTOR

BILLS OF QUANTITY

NAME OF THE WORK:-

Establishment of HWC at SC Sanimal in Sohela block of
Bargarh district for 2021-22.

AMOUNT PUT TO TENDER :-

Rs 439604.00

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	RATE IN FIGURE	AMOUNT (In Rs)
1	Removing old grading plaster from roof slab, cleaning the surface, lowering and removing the debris within 50M lead.	114.82	Sqm	60.20	(Rupees sixty and twenty paise only)	6912.16
2	Dismantling and removing 2.5cm th A.S.flooring including stacking the useful materials for reuse and ramming the debris with in 50m lead etc with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	50.07	Sqm	77.68	(Rupees seventy seven and sixty eight paise only)	3889.44
3	Removing old lime or cement plaster from walls including racking out joints 12mm deep and removing debris etc. with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	46.68	Sqm	38.84	(Rupees thirty eight and eighty four paise only)	1813.05
4	6mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment per 1 sqm	10.92	Sqm	130.75	(Rupees one hundred thirty and seventy five paise only)	1427.79
5	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	10.15	Cum	186.40	(Rupees one hundred eighty six and forty paise only)	1891.96
6	Supplying and filling in foundation and plinth with sand well watered & rammed with cost ,conveyance, royalty & taxes of all materials and labour required for the work as per specification and including 1% cess as per direction of the Engineer-in-Charge.	3.02	Cum	328.69	(Rupees three hundred twenty eight and sixty nine paise only)	992.64
7	Cement Concrete of proportion(1:3:6) in foundation and plinth using 4cm size clean hard black granite metal of approved quality from approved quarry including hoisting, lowering and laying in layers not exceeding 15cm thick to the required level, ramming watering and curing etc.complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	3.58	Cum	4095.79	(Rupees four thousand ninety five and seventy nine paise only)	14703.89
8	Cement concrete (1 : 2 : 4) using 12 mm size HG CB chips including laying lowering concrete, watering and curing & cost carriage royalty and taxes of all materials etc.	1.78	Cum	5429.89	(Rupees five thousand four hundred twenty nine and eighty nine paise only)	9665.20
9	2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size h.b.g. Chips per1 Sqm.	4.06	Sqm	269.42	(Rupees two hundred sixty nine and forty two paise only)	1093.85

10	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum. (In foundation)	4.04	Cum	4063.23	(Rupees four thousand sixty three and twenty three paise only)	16415.45
11	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum. (In Superstructure).	4.53	Cum	4096.56	(Rupees four thousand ninety six and fifty six paise only)	18557.42
12	12 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including waterreing and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	20.04	Sqm	133.59	(Rupees one hundred thirty three and fifty nine paise only)	2677.14
13	16 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including waterreing and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	24.91	Sqm	191.27	(Rupees one hundred ninety one and twenty seven paise only)	4764.54
14	Supplying, fitting and fixing of M.S. door, window and grill gate ... etc. complete as per direction of Engineer in charge.	750.68	Kg	82.18	(Rupees eighty two and eighteen paise only)	61690.88
15	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete excluding cost of precast tiles. (Ceramic Tiles)	46.68	Sqm	1047.39	(Rupees one thousand forty seven and thirty nine paise only)	48892.17
16	Supplying, fitting, fixing vetrified tiles in floors of following size of approved make confirming to IS: 13755 laid on 20mm thick cement mortar 1:4 (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour, T&P etc. required for the work all complete as per direction of Engineer-in-charge (For new work only)					
16.1	300mm x 300mm Vitrified industril floor tiles of premium grade 8mm to 10mm thick	11.15	Sqm	828.61	(Rupees eight hundred twenty eight and sixty one paise only)	9239.05
17	Providing and fixing vitrified tiles in floors, treads of steps and landing on 20mm th bed of cement mortar (1:4) (1 cement:4 sand) jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing, polishing including cost of tiles, conveyance, taxes & labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge	50.07	Sqm	939.27	(Rupees nine hundred thirty nine and twenty seven paise only)	47029.25

18	Providing & laying water proofs with polymeric bituminous membrane (Plastic felt) including priming the surface with bituminous primer including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	114.82	Sqm	315.38	(Rupees three hundred fifteen and thirty eight paise only)	36211.93
19	Priming one coat two wall surface using water bound cement primer including cost, conveyance all materials, labour and T & P etc complete.	44.95	Sqm	60.02	(Rupees sixty and two paise only)	2697.90
20	Finishing surface of walls with Acrylic putty (water based) of approved make & finished smooth & even surface to receive painting including cost of materials taxes labour etc.	643.55	Sqm	71.75	(Rupees seventy one and seventy five paise only)	46174.71
21	Distemping two coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper.	346.49	Sqm	125.35	(Rupees one hundred twenty five and thirty five paise only)	43432.52
22	Finishing walls with water proofing Weather coat (I.S.I.) of approved shade on old/new work two coat over a coat of primer to give an even shade including cost of Weather coat.	342.01	Sqm	127.26	(Rupees one hundred twenty seven and twenty six paise only)	43524.19
23	Painting two coats over a coat of primer with approved paint on wood work & Iron work. (Old & New)	82.08	Sqm	193.80	(Rupees one hundred ninety three and eighty paise only)	15907.10
					Total	Rs.439604.24

Or Say **Rs.439604.00**

(Rupees four lakh thirty nine thousand six hundred four) Only


Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:-Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost upto two decimal points only.

CONDITIONS:-All Materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B:-GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minium grade of cement OPC, TMT High strength steel Fe-500.


A.E. (NHM)
BARGARH


PROJECT DIRECTOR
DRDA BARGARH

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of

Rs. _____

only(both in figures and words).

CONTRACTOR

BILLS OF QUANTITY

NAME OF THE WORK:-

Establishment of HWC at SC Beherapali in Sohela block of
Bargarh district for 2021-22.

AMOUNT PUT TO TENDER :-

Rs 185889.00

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	RATE IN FIGURE	AMOUNT (In Rs)
1	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	1.36	Cum	186.40	(Rupees one hundred eighty six and forty paise only)	253.50
2	Supplying and filling in foundation and plinth with sand well watered & rammed with cost conveyance, royalty & taxes of all materials and labour required for the work as per specification and including 1% cess as per direction of the Engineer-in-Charge.	0.68	Cum	328.69	(Rupees three hundred twenty eight and sixty nine paise only)	223.51
3	Cement Concrete of proportion(1:3:6) in foundation and plinth using 4cm size clean hard black granite metal of approved quality from approved quarry including hoisting, lowering and laying in layers not exceeding 15cm thick to the required level, ramming watering and curing etc.complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	0.90	Cum	4095.79	(Rupees four thousand ninety five and seventy nine paise only)	3686.21
4	Cement concrete (1 : 2 : 4) using 12 mm size HG CB chips including laying lowering concrete, watering and curing & cost carriage royalty and taxes of all materials etc.	0.90	Cum	5429.89	(Rupees five thousand four hundred twenty nine and eighty nine paise only)	4886.90
5	Fixing tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete excluding cost of precast tiles (Ceramic Tiles)per 1 sqm	5.05	Sqm	980.44	(Rupees nine hundred eighty and forty four paise only)	4951.21
6	Supplying, fitting and fixing of M.S. door, window and grill gate ... etc. complete as per direction of Engineer in charge..	122.50	Kg	82.18	(Rupees eighty two and eighteen paise only)	10067.05
7	Supplying, fitting, fixing vetrified tiles in floors of following size of approved make confirming to IS: 13755 laid on 20mm thick cement mortar 1:4 (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour, T&P etc. required for the work all complete as per direction of Engineer-in-charge (For new work only)					
7.1	300mm x 300mm Vitrified industril floor tiles of premium grade 8mm to 10mm thick	6.04	Sqm	828.61	(Rupees eight hundred twenty eight and sixty one paise only)	5004.83

8	Providing, fitting & fixing of Al door with OEL anodized Al door section of 9202 as vertical member, 9201 as top member and 9200 as bottom and middle member and 6mm plain glass in top portion with 12mm thick prelaminated board in bottom portion fixed on door frame by means of tapered clip No 4660 and frame to be completed by means of jointing angle No.1855 including all cost of labour T & P hire charges of drilling machine labour charges etc complete.	1.95	Sqm	6562.96	(Rupees six thousand five hundred sixty two and ninety six paise only)	12797.78
9	Finishing surface of walls with Acrylic putty (water based) of approved make & finished smooth & even surface to receive painting including cost of materials taxes labour etc.	429.01	Sqm	71.75	(Rupees seventy one and seventy five paise only)	30781.47
10	Distemping two coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper.	240.03	Sqm	125.35	(Rupees one hundred twenty five and thirty five paise only)	30087.75
11	Finishing walls with water proofing Weather coat (I.S.I.) of approved shade on old/new work two coat over a coat of primer to give an even shade including cost of Weather coat.	559.92	Sqm	127.26	(Rupees one hundred twenty seven and twenty six paise only)	71255.42
12	Painting two coats over a coat of primer with approved paint on wood work & Iron work. (Old & New)	61.37	Sqm	193.80	(Rupees one hundred ninety three and eighty paise only)	11893.51
					Total	Rs.185889.15

Or Say **Rs.185889.00**

(Rupees one lakh eighty five thousand eight hundred eighty nine) Only

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:-Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost upto two decimal points only.

CONDITIONS:-All Materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B:-GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minimum grade of cement OPC, TMT High strength steel Fe-500.


A.E. (NHM)
BARGARH


PROJECT DIRECTOR
DRDA BARGARH

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of
Rs. _____

_____ only (both in figures and words).

CONTRACTOR

BILLS OF QUANTITY

NAME OF THE WORK:-

Establishment of HWC at SC Jaring in Bijepur block of Bargarh district for 2021-22.

AMOUNT PUT TO TENDER :-

Rs 386975.00

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	RATE IN FIGURE	AMOUNT (In Rs)
1	Removing old grading plaster from roof slab, cleaning the surface, lowering and removing the debris within 50M lead.	61.56	Sqm	60.20	(Rupees sixty and twenty paise only)	3705.91
2	Dismantling and removing 2.5cm th A.S flooring including stacking the useful materials for reuse and ramming the debris with in 50m lead etc with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	40.41	Sqm	77.68	(Rupees seventy seven and sixty eight paise only)	3139.05
3	Removing old lime or cement plaster from walls including racking out joints 12mm deep and removing debris etc. with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	30.85	Sqm	38.84	(Rupees thirty eight and eighty four paise only)	1198.21
4	6mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment per 1 sqm	10.92	Sqm	130.78	(Rupees one hundred thirty and seventy eight paise only)	1428.12
5	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	12.01	Cum	186.40	(Rupees one hundred eighty six and forty paise only)	2238.66
6	Supplying and filling in foundation and plinth with sand well watered & rammed with cost conveyance, royalty & taxes of all materials and labour required for the work as per specification and including 1% cess as per direction of the Engineer-in-Charge.	3.07	Cum	328.69	(Rupees three hundred twenty eight and sixty nine paise only)	1009.08
7	Cement Concrete of proportion(1:3:6) in foundation and plinth using 4cm size clean hard black granite metal of approved quality from approved quarry including hoisting, lowering and laying in layers not exceeding 15cm thick to the required level, ramming watering and curing etc. complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	3.49	Cum	4097.17	(Rupees four thousand ninety seven and seventeen paise only)	14299.12
8	Cement concrete (1 : 2 : 4) using 12 mm size HG CB chips including laying lowering concrete, watering and curing & cost carriage royalty and taxes of all materials etc.	1.30	Cum	5431.84	(Rupees five thousand four hundred thirty one and eighty four paise only)	7061.39
9	2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size h.b.g. Chips per 1 Sqm.	5.81	Sqm	269.47	(Rupees two hundred sixty nine and forty seven paise only)	1565.62

10	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum. (In foundation)	5.77	Cum	4063.63	(Rupees four thousand sixty three and sixty three paise only)	23447.15
11	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum. (In Superstructure).	6.46	Cum	4096.96	(Rupees four thousand ninety six and ninety six paise only)	26466.36
12	12 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including waterreing and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	28.62	Sqm	133.61	(Rupees one hundred thirty three and sixty one paise only)	3823.92
13	16 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including waterreing and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	35.59	Sqm	191.29	(Rupees one hundred ninety one and twenty nine paise only)	6808.01
14	Supplying, fitting and fixing of M.S. door, window and grill gate ... etc. complete as per direction of Engineer in charge..	417.31	Kg	82.18	(Rupees eighty two and eighteen paise only)	34294.54
15	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete excluding cost of precast tiles. (Ceramic Tiles)	30.85	Sqm	1047.47	(Rupees one thousand forty seven and forty seven paise only)	32314.45
16	Providing and fixing vitrified tiles in floors, treads of steps and landing on 20mm th bed of cement mortar (1:4) (1 cement:4 sand) jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing, polishing including cost of tiles, conveyance, taxes & labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge	40.41	Sqm	939.33	(Rupees nine hundred thirty nine and thirty three paise only)	37958.33
17	Providing & laying water proofs with polymeric bituminous membrance (Plastic felt) including priming the surface with bituminous primer including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	61.56	Sqm	315.38	(Rupees three hundred fifteen and thirty eight paise only)	19414.79
18	Priming one coat two wall surafce using water bound cement primer including cost, conveyance all materilas, labour and T & P etc complete.	64.21	Sqm	60.02	(Rupees sixty and two paise only)	3853.88
19	Finishing surface of walls with Acrylic putty (water based) of approved make & finished smooth & even surface to receive painting including cost of materials taxes labour etc.	644.31	Sqm	71.75	(Rupees seventy one and seventy five paise only)	46229.24

20	Distemping two coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper.	346.49	Sqm	125.35	(Rupees one hundred twenty five and thirty five paise only)	43432.52
21	Finishing walls with water proofing Weather coat (I.S.I.) of approved shade on old/new work two coat over a coat of primer to give an even shade including cost of Weather coat.	362.03	Sqm	127.26	(Rupees one hundred twenty seven and twenty six paise only)	46071.94
22	Painting two coats over a coat of primer with approved paint on wood work & Iron work. (Old & New)	82.27	Sqm	193.80	(Rupees one hundred ninety three and eighty paise only)	15943.93
23	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	78.49	Cum	143.59	(Rupees one hundred forty three and fifty nine paise only)	11270.38
					Total	Rs.386974.60
					Or Say	Rs.386975.00

(Rupees three lakh eighty six thousand nine hundred seventy five) Only

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:-Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost upto two decimal points only.

CONDITIONS:-All Materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B:-GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minium grade of cement OPC, TMT High strength steel Fe-500.


A.E. (NHM)
BARGARH


PROJECT DIRECTOR
DRDA BARGARH

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of

Rs. _____
_____ only (both in figures and words).

BILLS OF QUANTITY

NAME OF THE WORK:-

Establishment of HWC at SC Gathiapali in Bijepur block of
Bargarh district for 2021-22.

AMOUNT PUT TO TENDER :-

Rs 216973.00

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	RATE IN FIGURE	AMOUNT (In Rs)
1	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	7.36	Cum	186.40	(Rupees one hundred eighty six and forty paise only)	1371.90
2	Supplying and filling in foundation and plinth with sand well watered & rammed with cost ,conveyance, royalty & taxes of all materials and labour required for the work as per specification and including 1% cess as per direction of the Engineer-in-Charge.	2.69	Cum	328.69	(Rupees three hundred twenty eight and sixty nine paise only)	884.18
3	Cement Concrete of proportion(1:3:6) in foundation and plinth using 4cm size clean hard black granite metal of approved quality from approved quarry including hoisting, lowering and laying in layers not exceeding 15cm thick to the required level, ramming watering and curing etc.complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	3.28	Cum	4097.17	(Rupees four thousand ninety seven and seventeen paise only)	13438.72
4	Rigid and smooth centering and shuttering for C.C. works including labour and cost of materials complete etc & cost,conveyance,royalty and taxes as per direction of EIC.	11.15	Sqm	105.15	(Rupees one hundred five and fifteen paise only)	1172.39
5	Cement Concrete M10(1:3:6) with 12mm size hard granite metal including cost, conveyance, royalty ,taxes,watering and curing etc. complete.	1.70	Cum	4808.21	(Rupees four thousand eight hundred eight and twenty one paise only)	8173.96
6	Cement concrete (1 : 2 : 4) using 12 mm size HG CB chips including laying lowering concrete, watering and curring & cost carriage royalty and taxes of all materials etc.	2.43	Cum	5431.84	(Rupees five thousand four hundred thirty one and eighty four paise only)	13199.37

7	RCC work of M-20 grade with 20mm downgraded size hard granite chips including hoisting and laying					
7.1	Roof slab	0.37	Cum	8736.96	(Rupees eight thousand seven hundred thirty six and ninety six paise only)	3232.68
8	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification	0.33	Qtr	7661.51	(Rupees seven thousand six hundred sixty one and fifty one paise only)	2528.30
9	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum (In Superstructure)	0.71	Cum	4096.96	(Rupees four thousand ninety six and ninety six paise only)	2908.84
10	12 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including waterereing and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	11.15	Sqm	133.61	(Rupees one hundred thirty three and sixty one paise only)	1489.75
11	Fixing tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete excluding cost of precast tiles (Ceramic Tiles)per 1 sqm	2.08	Sqm	980.60	(Rupees nine hundred eighty and sixty paise only)	2039.66
12	Supplying, fitting, fixing vetrified tiles in floors of following size of approved make confirming to IS: 13755 laid on 20mm thick cement mortar 1:4 (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour, T&P etc. required for the work all complete as per direction of Engineer-in-charge (For new work only)					
12.1	300mm x 300mm Vitrified industril floor tiles of premium grade 8mm to 10mm thick	22.39	Sqm	828.68	(Rupees eight hundred twenty eight and sixty eight paise only)	18554.14
13	Finishing surface of walls with Acrylic putty (water based) of approved make & finished smooth & even surface to receive painting including cost of materials taxes labour etc.	507.71	Sqm	71.75	(Rupees seventy one and seventy five paise only)	36428.19
14	Distempering two coats to walls with distemper of approved shade on new work to give an even shade inculding cost of distemper.	297.94	Sqm	125.35	(Rupees one hundred twenty five and thirty five paise only)	37346.78
15	Finishing walls with water proofing Weather coat (I.S.I.) of approved shade on old/new work two coat over a coat of primer to give an even shade inculding cost of Weather coat.	424.20	Sqm	127.26	(Rupees one hundred twenty seven and twenty six paise only)	53983.69
16	Painting two coats with approved paint on wood work & Iron work. (Old & New)	137.18	Sqm	136.71	(Rupees one hundred thirty six and seventy one paise only)	18753.88

17	Earth work in filling by mechanical means etc complete as per the direction and specification of the Engineer-in-Charge.	4.29	Cum	341.84	(Rupees three hundred forty one and eighty four paise only)	1466.49
					Total	Rs.216972.91

Or Say

Rs.216973.00

(Rupees two lakh sixteen thousand nine hundred seventy three) Only

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:-Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost upto two decimal points only.

CONDITIONS:-All Materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B:-GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minimum grade of cement OPC, TMT High strength steel Fe-500.


AS (NHM)
BARGARH


PROJECT DIRECTOR
DRDA BARGARH

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of

Rs. _____

_____ only (both in figures and words).

CONTRACTOR

BILLS OF QUANTITY

NAME OF THE WORK:-

Establishment of HWC at SC Charpali in Bijepur block of
Bargah district for 2021-22.

AMOUNT PUT TO TENDER :-

Rs 439621.00

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	RATE IN FIGURE	AMOUNT (In Rs)
1	Removing old grading plaster from roof slab, cleaning the surface, lowering and removing the debris within 50M lead.	114.82	Sqm	60.20	(Rupees sixty and twenty paise only)	6912.16
2	Dismantling and removing 2.5cm th A.S. flooring including stacking the useful materials for reuse and ramming the debris with in 50m lead etc with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	50.07	Sqm	77.68	(Rupees seventy seven and sixty eight paise only)	3889.44
3	Removing old lime or cement plaster from walls including racking out joints 12mm deep and removing debris etc. with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	38.44	Sqm	38.84	(Rupees thirty eight and eighty four paise only)	1493.01
4	6mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment per 1 sqm	10.92	Sqm	130.78	(Rupees one hundred thirty and seventy eight paise only)	1428.12
5	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	13.39	Cum	186.40	(Rupees one hundred eighty six and forty paise only)	2495.90
6	Supplying and filling in foundation and plinth with sand well watered & rammed with cost ,conveyance, royalty & taxes of all materials and labour required for the work as per specification and including 1% cess as per direction of the Engineer-in-Charge.	3.77	Cum	328.69	(Rupees three hundred twenty eight and sixty nine paise only)	1239.16
7	Cement Concrete of proportion(1:3:6) in foundation and plinth using 4cm size clean hard black granite metal of approved quality from approved quarry including hoisting, lowering and laying in layers not exceeding 15cm thick to the required level, ramming watering and curing etc. complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	4.77	Cum	4097.17	(Rupees four thousand ninety seven and seventeen paise only)	19543.50
8	Cement concrete (1 : 2 : 4) using 12 mm size HG CB chips including laying lowering concrete, watering and curing & cost carriage royalty and taxes of all materials etc.	2.93	Cum	5431.84	(Rupees five thousand four hundred thirty one and eighty four paise only)	15915.29
9	2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size h.b.g. Chips per1 Sqm.	4.65	Sqm	269.47	(Rupees two hundred sixty nine and forty seven paise only)	1253.04

10	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum. (In foundation)	4.61	Cum	4063.63	(Rupees four thousand sixty three and sixty three paise only)	18733.33
11	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum. (In Superstructure).	5.17	Cum	4096.96	(Rupees four thousand ninety six and ninety six paise only)	21181.28
12	12 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including watereing and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	22.90	Sqm	133.61	(Rupees one hundred thirty three and sixty one paise only)	3059.67
13	16 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including watereing and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	28.47	Sqm	191.29	(Rupees one hundred ninety one and twenty nine paise only)	5446.03
14	Supplying, fitting and fixing of M.S. door, window and grill gate ... etc. complete as per direction of Engineer in charge..	731.92	Kg	82.18	(Rupees eighty two and eighteen paise only)	60149.19
15	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete excluding cost of precast tiles (Ceramic Tiles)	38.44	Sqm	1047.47	(Rupees one thousand forty seven and forty seven paise only)	40264.75
16	Providing and fixing vitrified tiles in floors, treads of steps and landing on 20mm th bed of cement mortar (1:4) (1 cement:4 sand) jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing, polishing including cost of tiles, conveyance, taxes & labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge	50.07	Sqm	939.33	(Rupees nine hundred thirty nine and thirty three paise only)	47032.25
17	Providing & laying water proofs with polymeric bituminous membrane (Plastic felt) including priming the surface with bituminous primer including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	114.82	Sqm	315.38	(Rupees three hundred fifteen and thirty eight paise only)	36211.93
18	Priming one coat two wall surafce using water bound cement primer including cost, conveyance all materilas, labour and T & P etc complete.	51.37	Sqm	60.02	(Rupees sixty and two paise only)	3083.23
19	Finishing surface of walls with Acrylic putty (water based) of approved make & finished smooth & even surface to receive painting including cost of materials taxes labour etc.	644.31	Sqm	71.75	(Rupees seventy one and seventy five paise only)	46229.24

20	Distemping two coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper.	346.49	Sqm	125.35	(Rupees one hundred twenty five and thirty five paise only)	43432.52
21	Finishing walls with water proofing Weather coat (I.S.I.) of approved shade on old/new work two coat over a coat of primer to give an even shade including cost of Weather coat.	349.19	Sqm	127.26	(Rupees one hundred twenty seven and twenty six paise only)	44437.92
22	Painting two coats over a coat of primer with approved paint on wood work & Iron work. (Old & New)	83.54	Sqm	193.80	(Rupees one hundred ninety three and eighty paise only)	16190.05
					Total	Rs.439621.00

Or Say

Rs.439621.00

(Rupees four lakh thirty nine thousand six hundred twenty one) Only

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:-Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost upto two decimal points only.

CONDITIONS:-All Materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B:-GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minium grade of cement OPC, TMT High strength steel Fe-500.


(NHM)
BARGARH


PROJECT DIRECTOR
DRDA BARGARH

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of

Rs. _____

_____ only (both in figures and words).

CONTRACTOR

BILLS OF QUANTITY

NAME OF THE WORK:-

Establishment of HWC at SC Budapali in Bijepur block of
Bargarh district for 2021-22.

AMOUNT PUT TO TENDER :-

Rs 451067.00

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	RATE IN FIGURE	AMOUNT (In Rs)
1	Removing old grading plaster from roof slab, cleaning the surface, lowering and removing the debris within 50M lead.	114.82	Sqm	60.20	(Rupees sixty and twenty paise only)	6912.15
2	Dismantling and removing 2.5cm th A.S flooring including stacking the useful materials for reuse and ramming the debris with in 50m lead etc with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	50.07	Sqm	77.68	(Rupees seventy seven and sixty eight paise only)	3229.44
3	Removing old lime or cement plaster from walls including racking out joints 12mm deep and removing debris etc. with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	46.68	Sqm	38.84	(Rupees thirty eight and eighty four paise only)	1813.05
4	6mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment per 1 sqm	10.92	Sqm	130.78	(Rupees one hundred thirty and seventy eight paise only)	1428.12
5	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	11.47	Cum	186.40	(Rupees one hundred eighty six and forty paise only)	2138.01
6	Supplying and filling in foundation and plinth with sand well watered & rammed with cost ,conveyance, royalty & taxes of all materials and labour required for the work as per specification and including 1% cess as per direction of the Engineer-in-Charge.	3.09	Cum	328.69	(Rupees three hundred twenty eight and sixty nine paise only)	1015.65
7	Cement Concrete of proportion(1:3:8) in foundation and plinth using 4cm size clean hard black granite metal of approved quality from approved quarry including hoisting, lowering and laying in layers not exceeding 15cm thick to the required level, ramming watering and curing etc.complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	3.57	Cum	4097.17	(Rupees four thousand ninety seven and seventeen paise only)	14626.90

8	Cement concrete (1 : 2 : 4) using 12 mm size HG CB chips including laying lowering concrete, watering and curing & cost carriage royalty and taxes of all materials etc.	1.50	Cum	5431.84	(Rupees five thousand four hundred thirty one and eighty four paise only)	8147.76
9	2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size h.b.g. Chips per 1 Sqm.	5.23	Sqm	269.47	(Rupees two hundred sixty nine and forty seven paise only)	1409.33
10	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum (In foundation)	5.19	Cum	4063.63	(Rupees four thousand sixty three and sixty three paise only)	21090.24
11	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum (In Superstructure)	5.82	Cum	4096.96	(Rupees four thousand ninety six and ninety six paise only)	23844.31
12	12 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including watering and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	25.76	Sqm	133.61	(Rupees one hundred thirty three and sixty one paise only)	3441.79
13	16 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including watering and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	32.02	Sqm	191.29	(Rupees one hundred ninety one and twenty nine paise only)	6125.11
14	Supplying, fitting and fixing of M.S. door, window and grill gate ... etc. complete as per direction of Engineer in charge.	550.34	Kg	82.18	(Rupees eighty two and eighteen paise only)	45226.94
15	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete excluding cost of precast tiles (Ceramic Tiles)	46.68	Sqm	1047.47	(Rupees one thousand forty seven and forty seven paise only)	48895.90

16	Supplying, fitting, fixing vetrified tiles in floors of following size of approved make confirming to IS: 13755 laid on 20mm thick cement mortar 1:4 (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour, T&P etc. required for the work all complete as per direction of Engineer-in-charge (For new work only)					
16.1	300mm x 300mm Vitrified industril floor tiles of premium grade 8mm to 10mm thick	9.10	Sqm	828.68	(Rupees eight hundred twenty eight and sixty eight paise only)	7540.99
17	Providing and fixing vitrified tiles in floors, treads of steps and landing on 20mm th bed of cement mortar (1:4) (1 cement:4 sand) joined with neat cement slurry mixed with pigment to match the shade of tiles including rubbing, polishing including cost of tiles, conveyance, taxes & labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge	50.07	Sqm	939.33	(Rupees nine hundred thirty nine and thirty three paise only)	47032.25
18	Providing & laying water proofs with polymeric bituminous membrance (Plastic felt) including priming the surface with bituminous primer including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	114.82	Sqm	315.38	(Rupees three hundred fifteen and thirty eight paise only)	36211.93
19	Supplying ,fitting ,fixing of stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32x32x2mm @0.90 mtr. C/C and stainless square pipe bracing of size 32x32x2mm in 3 rows in stair case as per approved design and specification, buffing , polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc required for the coplete in all respect.	4.27	Rm	3805.37	(Rupees three thousand eight hundred five and thirty seven paise only)	16248.91
20	Priming one coat two wall surafce using water bound cement primer including cost, conveyance all materilas, labour and T & P etc complete.	57.78	Sqm	60.02	(Rupees sixty and two paise only)	3467.96
21	Finishing surface of walls with Acrylic putty (water based) of approved make & finished smooth & even surface to receive painting including cost of materials taxes labour etc.	642.94	Sqm	71.75	(Rupees seventy one and seventy five paise only)	46130.95
22	Distempering two coats to walls with distemper of approved shade on new work to give an even shade inculding cost of distemper.	346.49	Sqm	125.35	(Rupees one hundred twenty five and thirty five paise only)	43432.52
23	Finishing walls with water proofing Weather coat (I.S.I.) of approved shade on old/new work two coat over a coat of primer to give an even shade inculding cost of Weather coat.	354.22	Sqm	127.26	(Rupees one hundred twenty seven and twenty six paise only)	45078.04

24	Painting two coats over a coat of primer with approved paint on wood work & Iron work. (Old & New)	82.14	Sqm	193.80	(Rupees one hundred ninety three and eighty paise only)	15918.73
					Total	Rs.451066.98
					Or Say	Rs.451067.00

(Rupees four lakh fifty one thousand sixty seven) Only

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:-Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost upto two decimal points only.

CONDITIONS:-All Materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B:-GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minium grade of cement OPC, TMT High strength steel Fe-500.


(NHM)
BARGARH


PROJECT DIRECTOR
DRDA BARGARH

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of

Rs. _____
_____ only(both in figures and words).

CONTRACTOR

BILLS OF QUANTITY

NAME OF THE WORK:-

Establishment of HWC at SC Badipali in Bijepur block of
Bargarh district for 2021-22.

AMOUNT PUT TO TENDER :-

Rs 335060.00

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE (In Rs)	RATE IN FIGURE	AMOUNT (In Rs)
1	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the EIC.	1.24	Cum	186.40	(Rupees one hundred eighty six and forty paise only)	231.14
2	Supplying and filling in foundation and plinth with sand well watered & rammed with cost, conveyance, royalty & taxes of all materials and labour required for the work as per specification and including 1% cess as per direction of the Engineer-in-Charge.	0.31	Cum	328.69	(Rupees three hundred twenty eight and sixty nine paise only)	101.89
3	Cement Concrete of proportion (1:3:6) in foundation and plinth using 4cm size clean hard black granite metal of approved quality from approved quarry including hoisting, lowering and laying in layers not exceeding 15cm thick to the required level, ramming watering and curing etc. complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	0.41	Cum	4097.17	(Rupees four thousand ninety seven and seventeen paise only)	1679.84
4	Cement concrete (1:2:4) using 12 mm size HG CB chips including laying lowering concrete, watering and curing & cost carriage royalty and taxes of all materials etc.	1.59	Cum	5431.84	(Rupees five thousand four hundred thirty one and eighty four paise only)	8636.63
5	Fly Ash brick work with 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in foundation and plinth per cum. (In foundation & Plinth)	1.03	Cum	4063.63	(Rupees four thousand sixty three and sixty three paise only)	4185.54
6	12 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including watering and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	10.83	Sqm	133.61	(Rupees one hundred thirty three and sixty one paise only)	1447.00

7	Providing and fixing vitrified tiles in floors, treads of steps and landing on 20mm th bed of cement mortar (1:4) (1 cement:4 sand) jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing, polishing including cost of tiles, conveyance, taxes & labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge	45.01	Sqm	939.33	(Rupees nine hundred thirty nine and thirty three paise only)	42279.26
8	Providing Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete excluding cost of precast tiles.(Ceramic Tiles)	6.10	Sqm	1047.47	(Rupees one thousand forty seven and forty seven paise only)	6389.57
9	Fixing tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete excluding cost of precast tiles (Ceramic Tiles)per 1 sqm	2.45	Sqm	980.60	(Rupees nine hundred eighty and sixty paise only)	2402.48
10	Supplying, fitting, fixing vetrified tiles in floors of following size of approved make confirming to IS: 13755 laid on 20mm thick cement mortar 1:4 (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour, T&P etc. required for the work all complete as per direction of Engineer-in-charge (For new work only)					
10.1	300mm x 300mm Vitrified industril floor tiles of premium grade 8mm to 10mm thick	39.02	Sqm	828.68	(Rupees eight hundred twenty eight and sixty eight paise only)	32335.09
11	Finishing surface of walls with Acrylic putty (water based) of approved make & finished smooth & even surface to receive painting includng cost of materials taxes labour etc.	797.54	Sqm	71.75	(Rupees seventy one and seventy five paise only)	57223.50
12	Distemping two coats to walls with distemper of approved shade on new work to give an even shade inculding cost of distemper.	503.55	Sqm	125.35	(Rupees one hundred twenty five and thirty five paise only)	63119.99
13	Finishing walls with water proofing Weather coat (I.S.I.) of approved shade on old/new work two coat over a coat of primer to give an even shade inculding cost of Weather coat.	696.06	Sqm	127.26	(Rupees one hundred twenty seven and twenty six paise only)	88580.60

14	Painting two coats over a coat of primer with approved paint on wood work & Iron work. (Old & New)	136.47	Sqm	193.80	(Rupees one hundred ninety three and eighty paise only)	26447.89
					Total	Rs.335060.39

Or Say **Rs.335060.00**

(Rupees three lakh thirty five thousand sixty) only


Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes:-Contractor should not write anything except quoting of Percentage, Excess/ Less /Equal to the total Estimated cost upto two decimal points only.

CONDITIONS:-All Materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B:-GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works the minium grade of cement OPC, TMT High strength steel Fe-500.


A. E. N. H. M.
BARGARH


PROJECT DIRECTOR
DRDA BARGARH

My/Our quoted rate is _____ % Excess over/Less than/Equal to the above tendered amount of

Rs. _____

_____ only(both in figures and words).

CONTRACTOR

BILLS OF QUANTITY

Establishment of HWC at SC Kubedega in Bheden block of Bargarh district for 2021-22
230685.00

NAME OF WORK -

AMOUNT PUT TO TENDER-

Sl. No	Item of work	Unit	Quantity	Rate	Rate in word	Amount
1	Earth work excavation of foundation in hard soil with all leads and lifts including dressing the sides and levelling the bed of foundation including cost of all labour required for the work etc complete with all other T&P required for the work and stacking the excavated materials away from working area as directed by the Engineer-in-charge including 1% cess.	Cum	1.70	186.39	(Rupees One Hundred Eighty Six and thirty nine paise only)	316.49
2	Supplying and filling in foundation and plinth with sand well watered & rammed with cost conveyance, royalty & taxes of all materials and labour required for the work as per specification and including 1% cess as per direction of the Engineer-in-Charge.	Cum	0.57	321.75	(Rupees three hundred twenty one and seventy five paise only)	182.11
3	Cement Concrete of proportion(1:3:6) in foundation and plinth using 4cm size clean hard black granite metal of approved quality from approved quarry including hoisting, lowering and laying in layers not exceeding 15cm thick to the required level, ramming watering and curing etc complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P and cess etc. complete in all respect as per specification and direction of the Engineer in-charge.	Cum	0.42	4116.76	(Rupees four thousand one hundred sixteen and seventy six paise only)	1745.51
4	R.C.C. work of in CC M20 with 20 mm and down graded size black hard granite (crusherbroken) stone chips including hoisting and laying					0.00
4.1	Shelves	Sqm	6.69	717.28	(Rupees seven hundred seventeen and twenty eight paise only)	4797.18
5	Cutting, Straightening the bend up M.S./Tor Rods bending, binding welding, jointing if necessary and tying the grills and placing in position as required for R.C.C. works and for providing required no of fan hooks hoisting, lowering, laying including cost, conveyance and taxes of M.S. Rods or Tor steel and binding wires of 18 to 20 gauge required for the work bending, binding and tying the grills in all floors (payment will be made on weight of M.S. rods or Tor steel only and no separate payment will be made towards the weight of binding wires) including 1% cess as per direction of the Engineer-in-charge.	Qtl	0.36	7741.22	(Rupees seven thousand seven hundred forty one and twenty two paise only)	2786.84
6	Fly Ash brick masonry in C:M (1:6) using 25cmx12cmx8 cm size bricks having crushing strength of not less than 75 Kg. per sq.cm. including splays cutting, circular, mouldings, and corbelling, champhering and similar such type of work, watering and curing etc. complete including cost, conveyance, royalties and taxes of all materials and cost of all labour with T&P required for the work etc. complete including 1% cess and as per the specification as directed by the Engineer-in-charge.	Cum	1.51	4070.52	(Rupees four thousand seventy and fifty two paise only)	6142.41

7	Cement concrete of proportion (1:2:4) using 20mm size hard granite chips of approved quality from approved quarry including hoisting, lowering and laying concrete and compacting in layers not exceeding 15cm thick with proper packing and ramming each layer of concrete by means of vibrator including watering and curing etc. complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P etc. complete in all respect as per specification and direction of the Engineer in-charge.	Cum	0.42	5459.49	(Rupees five thousand four hundred fifty nine and forty nine paise only)	2314.82
8	16 mm thick cement plaster in C.M. (1:6) over brick masonry finished smooth after racking out of the joints including watering and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour and T&P required for the work including 1% cess as directed by the Engineer-in-charge.	Sqm	8.45	191.64	(Rupees one hundred ninety one and sixty four paise only)	1619.93
9	6mm thick cement Plaster (1:4) RCC Surface finished smooth including closed deep shing and slurry treatment. With cost of all charges etc complete as per the direction of Engineer-in charge.	Sqm	1.67	150.58	(Rupees one hundred fifty and fifty eight paise only)	251.77
10	12mm th Cement plaster in C.M (1:6) to brick work finished smooth including watering curing and scaffolding with cost, conveyance, royalty, taxes of all the materials required for the work with all labour, T&P etc. complete in all respect as per specification and direction of the Engineer-in-charge.	Sqm	13.11	133.88	(Rupees one hundred thirty three and eighty eight paise only)	1755.70
11	Distemping two coats with approved shade with cost, conveyance, taxes of all the materials required for the work and labour, T&P etc. complete in all respect as per specification and direction of the Engineer-in-charge.	Sqm	304.49	121.83	(Rupees one hundred twenty one and eighty three paise only)	37096.01
12	Weather coat two coats including cost, conveyance, taxes of all materials all labour and T & P required for the work etc complete including 1% cess as per direction of the Engineer in charge.	Sqm	471.56	119.97	(Rupees one hundred nineteen and ninety seven paise only)	56573.61
13	Finishing surface of walls with cement based wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding, staging charges with cost of all materials, taxes, labour T&P and cess etc. complete in all respect as per specification and direction of the Engineer-in-charge.	Sqm	463.90	71.75	(Rupees seventy one and seventy five paise only)	33285.04
14	Supplying, of M.S doors and windows shutters of approved design in proper position making good to the damages of walls of R.C.C or other structural etc. including mending or cutting sizes or grooves in chaukhats with cost, conveyance, taxes of all materials required for the work, labour and T&P etc. complete as per specification and direction of the E.I.C.	Kg	26.25	82.00	(Rupees eighty two only)	2152.50

15	Supplying, fitting and fixing of MS pipe of approved size and quality with cost of all charges etc complete.	Kg	345.00	82.00	(Rupees eighty two only)	28290.00
16	Supplying, of M S grill for window and ventilator of approved design in proper position making good to the damages of walls of R.C.C or other structural etc. including mending or cutting sizes or grooves in chaukhats with cost, conveyance, taxes of all materials required for the work, labour and T&P etc. complete as per specification and direction of the E.I.C.	Kg	37.50	80.00	(Rupees eighty only)	3000.00
17	Supplying, fitting & fixing Colour coated Durashine Roofing sheet of size 0.45mm (TCT)X 1072mm in roof including cost of sheet & all charges e.t.c. all complete.	Sqm	20.44	769.72	(Rupees seven hundred sixty nine and seventy two paise only)	15731.54
18	Painting two coats over a coat of primer with any approved paint with brush to wall surface including cost, conveyance, taxes of all the materials required for the work with all labour, T&P etc. complete as per specification and direction of the Engineer-in-charge.	Sqm	71.38	187.61	(Rupees one hundred eighty seven and sixty one paise only)	13391.93
19	300mm x 300mm Vitrified industrial floor tiles of premium grade 8mm to 10mm thickon 12mm th cement plaster (1:3) (1cement:3sand) joined with neat cement slurry mixed with pigment to match the shade of tiles, rubbing, polishing including cost of tiles, conveyance, taxes & labour, T&P etc. complete as per specification and direction of E.I.C.	Sqm	23.23	828.88	(Rupees eight hundred twenty eight and eighty eight paise only)	19250.74
				Total	Rs.	230684.14
					Or, Say Rs.	230685.00


(Rupees two lakh thirty thousand six hundred eighty five only)

Total No pages (Enclosed) other than DTCN-----pages.

Notes:- The contractor should not write any thing except quoting of percentage, Excess/Less/Equal to the estimate upto two decimal point only.

CONDITION :- All materials, Labour, Machinery and equipment required to complete the work in all respect be arranged by the tenderer at his own cost. The employer will bear no responsibility in this aspect.

N.B. :- GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the contractor for all above works, the minimum grade of cement shall be OPC, TMT High strength steel Fe- 500.


A. B. NHM
BARGARH


PROJECT DIRECTOR
DRDA, BARGARH

My/Our quoted rate is (both in figure & words) Excess over/ Less than/
Equal to the above tendered amount of Rs
..... Only

CONTRACTOR